

A HARMONISED POINT-EXTRACTION AND COMPARISON TOOL FOR HETEROGENEOUS PALEOCLIMATE DATASETS

Levin Damian Antonin Giersch

Student ID: 0515040
E-Mail: l.giersch@campus.tu-berlin.de
Faculty: Faculty VI - Planning Building Environment
Program: Geodesy and Geoinformation Science, M.Sc.
Lecturer: Prof. Dr.-Ing. Martin Kada
Date: 14th June 2026

KEY WORDS: Paleoclimate, Data harmonisation, Paleoclimate datasets, Temperature comparison, TraCE-21k, CHELSA-TraCE21k-centennial, PalMod2, Beyer2020

ABSTRACT:

Transient paleoclimate simulations and reconstructions are indispensable for understanding how the Earth system responds to forcing, yet they are distributed in mutually incompatible formats. Each archive uses a different time origin and unit, a different spatial grid and longitude convention, a different temperature variable, and a different temporal and spatial resolution. This project develops a small, reproducible Python toolchain that downloads four widely used temperature archives covering the last glacial cycle, namely TraCE-21k, CHELSA-TraCE21k-centennial, Beyer2020 and PalMod2. It harmonises their time axes onto a common kiloyears-before-present (ka BP) scale, reconciles their spatial grids, converts all temperatures to degrees Celsius, and then extracts and compares temperature time series at an arbitrary point as well as globally through pairwise mean-difference heatmaps. Applied to an example location in northern Germany ($\approx 53.26^\circ\text{N}$, 11.67°E), the four archives agree on the first-order signal, a cold Last Glacial Maximum (LGM) followed by deglacial warming into the Holocene, but disagree on absolute temperature by several degrees, with the largest systematic divergences at high northern latitudes and in mountain regions. The report documents the datasets, the acquisition and pre-processing pipeline, the harmonisation methods and the results, and discusses why these archives are difficult to compare and what the comparison reveals.

1. INTRODUCTION

1.1 Why paleoclimate models matter

Instrumental temperature records span at most the last ~ 320 years (Wetterdienst, n.d.), far too short to characterise the full range of natural climate variability or to observe the slow processes (ice-sheet growth and decay, ocean-circulation reorganisations, orbital forcing) that govern the climate system on millennial timescales. Numerical paleoclimate simulations and data-constrained reconstructions extend our knowledge of temperature across the last glacial cycle and beyond. They are useful for: reconstructing Earth's climate before direct measurements existed, understanding how the climate responds to forcings such as solar output, volcanic eruptions, Milanković cycles, greenhouse gases and changing ice sheets, testing and validating modern climate models against known past states, establishing the natural variability range of climate, separate from human influence, constraining climate sensitivity (the temperature change per CO_2 doubling) using the large glacial-interglacial signal and using past warm periods as analogues for near-future projections.

1.2 Why intercompare models

No single archive is “correct”. Coupled general-circulation models (GCMs) such as those behind TraCE-21k and PalMod2 simulate the physics explicitly but at coarse resolution; statistical reconstructions and downscaling products such as Beyer2020 and CHELSA-TraCE21k-centennial achieve high

spatial resolution by anchoring model output to present-day observations, at the cost of the assumptions built into the downscaling. Comparing them is therefore important: systematic differences reveal where the archives are robust and where they diverge, expose outliers and artefacts, and help target the processes or regions where the underlying models most need improvement. A comparison cannot say which archive is right, but it can say where and by how much they disagree.

1.3 Aim and scope

The aim of this project is a harmonised point-extraction and comparison tool for four heterogeneous paleoclimate temperature archives. Given a latitude and longitude, the tool extracts a near-surface air-temperature (and, where available, soil-temperature) time series from each archive, reconciles their incompatible time axes, spatial grids and units, and produces (i) per-dataset inspection reports, (ii) a temperature time-series overlay at the requested point, (iii) a side-by-side summary of temporal coverage and the grid cell each archive returns near the point, and (iv) global pairwise mean-difference heatmaps. The workflow is organised as three Jupyter notebooks: a downloader, a pre-processor, and the comparison and exploration notebook (Giersch, 2026).

1.4 Study area and example point

All point-based results below are shown for a single terrestrial location in northern Germany ($\approx 53.26^\circ\text{N}$, 11.67°E , south-western Mecklenburg, near the lower Elbe). The location is

used purely as a worked example; the tool accepts any coordinate. It is mid-latitude, continental and ice-free throughout the studied interval, which makes it a convenient case for examining how the four archives represent the deglacial warming at one place.

2. THE DATA

Four archives were selected to span the trade-off between temporal resolution, spatial resolution and time coverage. Two are raw transient GCM simulations (TraCE-21k, PalMod2); two are high-resolution, observation-anchored products (Beyer2020, CHELSA-TraCE21k-centennial). Table 1 summarises them. All are downloaded via the `data_downloader` notebook; the total download is on the order of 1 TB, dominated by the ~ 1 km CHELSA-TraCE21k-centennial GeoTIFFs.

2.1 TraCE-21k

TraCE-21k (the “Simulation of the Transient Climate of the Last 21,000 Years”, here the TraCE-21k Main Land Decadal Average product) is a fully coupled, non-accelerated atmosphere-ocean-sea-ice-land-surface transient simulation produced with the Community Climate System Model version 3 (CCSM3), its land component being the Community Land Model 2 (CLM2). It integrates forward from the LGM under transient orbital, greenhouse-gas, ice-sheet and meltwater forcing and is one of the foundational transient deglaciation experiments. The atmosphere and land grid is T31_gx3 ($\sim 3.75^\circ$, 96 longitudes $\times$ 48 latitudes). The used variables are TSA (2 m air temperature) and TSOI (soil temperature on 10 layers), delivered as two NetCDF files of ≈ 449 MB; time runs from 22 ka BP to present as decadal averages (2204 steps). Access is via the NCAR GDEX archive (dataset d651050); variable codes are listed in the TraCE-21k variable table. Source: (Otto-Bliesner and Rosenbloom, 2021) (CCSM3 TraCE simulations fields complete list, n.d.).

2.2 CHELSA-TraCE21k-centennial

CHELSA-TraCE21k-centennial is a high-resolution (~ 1 km) downscaled product of transient temperature and precipitation since the LGM, generated with the CHELSA-TraCE21k downscaling model (Karger et al., 2023, Karger et al., 2020). The centennial variant used here provides monthly climatologies at 100-year time steps, at a native resolution of ~ 1 km (30 arcsec, $\approx 0.0083^\circ$), globally. The used variables are `tasmax` and `tasmin`; the mean air temperature is derived as `tasmean` = $(\text{tasmax} + \text{tasmin})/2$ in the `data_processor` notebook (Giersch, 2026). The data arrive as GeoTIFF (one raster per month, per time index, per variable) and must be converted to NetCDF; coverage is 22 ka BP to present in centennial steps (221 time steps). The ~ 1 km tiffs dominate the download. Source: (Karger et al., 2023); data (Karger et al., 2020).

2.3 Beyer2020

Beyer2020 (version-4 / “2021” update is used) reconstructs high-resolution terrestrial climate, bioclimate and vegetation for the last 120,000 years, produced at the Department of Zoology, University of Cambridge (Beyer et al., 2020, Beyer et al., 2021). It was built by a delta-method downscaling and bias-correction procedure that combines medium-resolution transient HadCM3 simulations with high-resolution HadAM3H time-slice snapshots and present-day observational climatology,

bridging the gap between high-temporal-resolution but coarse simulations and high-spatial-resolution but snapshot-only datasets. The used variable is temperature (monthly mean, $^\circ\text{C}$), delivered as a single bundled NetCDF on a 0.5° equirectangular grid (720×300 , ~ 55 km at the equator), global terrestrial only (latitudes ≈ 60 S to 90 N). Coverage is 120 ka BP to pre-industrial in 72 snapshots, with 2000-year steps from 120–22 ka BP and 1000-year steps from 22–0 ka BP. The v4 release adds global monthly NPP relative to v3, documented in the 2021 addendum. Source: (Beyer et al., 2020), (Beyer et al., 2021) and (Beyer, 2021).

2.4 PalMod2

PalMod2 here denotes the MPI-M MPI-ESM1-2-CR Transient Simulations of the Last Deglaciation with prescribed ice sheets from GLAC-1D reconstructions (r11p1f1), produced at the Max Planck Institute for Meteorology and DKRZ (Mikolajewicz et al., 2023). It is a fully coupled transient simulation with MPI-ESM1.2 in coarse resolution (MPI-ESM1.2-CR): the ECHAM6.3 spectral atmosphere at T31 (96×48 , 31 levels), the JSBACH3.20 land surface, and the MPIOM1.63 ocean (~ 300 km), with realistic time-evolving ice-sheet, topography and land-sea-mask forcing from GLAC-1D. The used variables are `tas` (near-surface, usually 2 m, air temperature; PMMXMCRTDGr111Amtasgn30201) and `ts1` (soil temperature by layer; PMMXMCRTDGr111Lmtslgn30201), both monthly, in K; the native time coverage is the last ~ 25 kyr. Access is through the WDCC archive at DKRZ, downloaded via the `jb1ob` client after registration (World Data Center for Climate and Deutsches Klimarechenzentrum, n.d.); model output is licensed CC-BY-SA 4.0. Source: (Mikolajewicz et al., 2023).

2.5 Data acquisition

Each archive uses a different access mechanism (Table 2). PalMod2 is the only one requiring authentication: a WDCC account must be created (registration may take several days) and the `jb1ob` client obtained from the WDCC site. The downloader skips files that already exist, so it is safe to re-run.

3. PRE-PROCESSING

Two of the four archives cannot be used as delivered. The `data_processor` notebook performs the necessary conversions; TraCE-21k and Beyer2020 are already analysis-ready NetCDF and are passed through unchanged.

3.1 CHELSA-TraCE21k-centennial: GeoTIFF to centennial-mean NetCDF

The CHELSA-TraCE21k-centennial product arrives as one GeoTIFF per month, per time index, per variable, named `CHELSA_TraCE21k_<var>_<MM>_<TTT>_V.1.0.tif`, where `MM` is the month and `TTT` a centennial time index. The `data_processor` notebook first groups files by year: a regex extracts month and index, and the index is mapped to a calendar year by year = $1990 - (20 - \text{TTT}) \times 100$, anchored at $\text{TTT} = 20 \rightarrow 1990$ CE with 100-year steps. Thus index 0 maps to about year -10 CE and index -200 to about -20010 CE (≈ 22 ka BP, near the LGM). This mapping is consistent with the file’s `frequency=centennial` metadata, the $\sim 21,000$ -year nominal coverage and the file count ($221 \text{ steps} \times 100 \text{ years} \approx 22 \text{ kyr}$); the exact index-to-year table is not published by CHELSA-TraCE21k-centennial, so the mapping is a

Dataset	Type	Variables	Coverage	Time step	Native res.	Unit
TraCE-21k	Coupled GCM (CCSM3)	TSA, TSOI	22–0 ka BP	decadal	T31 ($\sim 3.75^\circ$)	K
PalMod2	Coupled GCM (MPI-ESM1.2-CR)	tas, tsl	25–0 ka BP	annual	T31 ($\sim 3.71^\circ$)	K
Beyer2020/21 (v4)	Downscaled reconstruction	temperature	120–0 ka BP	2/1 kyr	0.5°	$^\circ\text{C}$
CHELSEA-TraCE21k-centennial	Downscaled product	tasmean	22–0 ka BP	centennial	~ 1 km (30 arcsec)	K

Table 1. Overview of the four temperature archives.

Dataset	Host	Mechanism
TraCE-21k	NCAR GDEX (d651050)	Direct HTTP; filtered to TSA/TSOI.
CHELSEA-TraCE21k-centennial	EnviDat / SwitchCH S3	Parallel download (32 threads), atomic <code>.part</code> rename.
Beyer2020	figshare API	Query API for version 4 of article 12293345.
PalMod2	WDCC / DKRZ	jb1ob client, login automated via <code>pexpect</code> .

Table 2. Acquisition mechanism per dataset.

well-constrained reconstruction, flagged as such in the notebook. For each year the 12 monthly rasters are stacked and averaged to one (lat, lon) field; CHELSA-TraCE21k-centennial stores temperature as $\text{Kelvin} \times 10$, so a factor of 0.1 is applied and the result cast back to `float32`. All years are concatenated along a new time axis (one timestamp at 1 July of each year), tagged with CF-style metadata, and written as one gzip-compressed NetCDF per variable at the full native ~ 1 km resolution. Finally `tasmean = (tasmin + tasmax)/2` is derived. (Giersch, 2026)

Because the full-resolution inputs are very large (on the order of ~ 100 GB each), every step before the write is lazy: only a Dask task graph is built. Data are materialised chunk by chunk during `to_netcdf`, so peak memory is set by the chunk size ($4500 \times 2250 \times 4$ bytes ≈ 40 MB) times the number of workers, not by the full array. The `astype("float32")` after each floating-point operation is deliberate: multiplying by a Python float upcasts to `float64`, and casting back keeps the data at 4 bytes per pixel.

3.2 PalMod2: monthly to annual means and merge

The PalMod2 `tas` and `tsl` variables are delivered as monthly NetCDF files (250 per variable). For each variable the processor applies `cdo yearmean` to collapse the 12 monthly values of each file into annual means, then `cdo mergetime` to concatenate all annual-mean files along the time axis. To keep CDO from ever seeing the space-containing project path, the commands run from within the extraction directory using relative filenames. The merged outputs have 25,000 annual time steps.

4. HOMOGENISATION

The four archives cannot be compared until they share a common footing in variable, time, space and unit. This is the analytical core of the project, performed in the `paleoclimate_comparison` notebook. (Giersch, 2026)

4.1 Variables

The comparison restricts itself to near-surface air temperature (and, separately, soil temperature), the only quantities common to enough archives to be comparable. Even so the variables are not strictly identical (Table 3): TraCE-21k `TSA` and PalMod2 `tas` are model 2 m air temperatures; Beyer2020 `temperature` is a downscaled, bias-corrected monthly mean;

CHELSEA-TraCE21k-centennial `tasmean` is the mean of downscaled daily extremes. These are physically close but not interchangeable, a caveat carried into the results. For soil temperature, only PalMod2 and TraCE-21k provide a layered variable; the comparison keeps the topmost soil layer (for TraCE, `levsoi[0]  $\approx 0.007$  m`).

4.2 Time

Every archive encodes time differently (different origin, sign convention and unit), so a single function, `time_to_ka_bp`, centralises the translation to a common scale of kiloyears before present, with the past positive and the present at zero (Table 4). For the two “days since” archives the absolute reference date is irrelevant: only the elapsed time before the most recent sample matters, so the conversion anchors on `vals.max()` and divides by $365250 = 1000 \times 365.25$ days ($= 1$ kyr in a proleptic-Gregorian calendar). The ~ 0.5 ka rounding this can introduce is invisible on a 0–125 ka axis. After conversion the four archives span, respectively, 0–120 ka (Beyer), 0–25 ka (PalMod2) and 0–22 ka (TraCE, CHELSA-TraCE21k-centennial) BP. The temporal resolution also differs by three orders of magnitude (annual, decadal, centennial and 1–2 kyr), which directly affects how much high-frequency variability each archive exposes.

4.3 Space

The archives sit on four grids (Table 5) and use two longitude conventions (0 – 360° and -180 – 180°). The tool detects latitude and longitude coordinates by name and, before any query, converts a requested negative longitude to 0 – 360° when the file demands it. The spatial-resolution mismatch is severe: a single PalMod2 or TraCE-21k cell ($\sim 3.7^\circ$) is roughly $250 \text{ km} \times 410 \text{ km}$ at 53°N , whereas a CHELSA-TraCE21k-centennial pixel (0.0083°) is about 1 km and a Beyer2020 cell (0.5°) about 55 km . PalMod2 and TraCE-21k share the same T31 grid, so their cells coincide exactly.

4.4 Units

PalMod2, TraCE-21k and CHELSA-TraCE21k-centennial store temperature in kelvin; Beyer2020 in degrees Celsius. All extracted series are converted to $^\circ\text{C}$ (subtracting 273.15 K where required) before plotting or differencing, so every figure is in a single, intuitive unit.

Dataset	Air var.	Soil var.	Unit	Native averaging
Beyer2020	temperature	–	°C	monthly → annual
PalMod2	tas	tsl (layer)	K	monthly → annual
TraCE-21k	TSA	TSOI (layer)	K	decadal average
CHELSA-TraCE21k-centennial	tasmean	–	K	centennial clim.

Table 3. Temperature variables harmonised.

Dataset	units attribute	Raw range	Conversion
Beyer2020	years since present (past negative)	[−120000, 0]	−vals/1000
PalMod2	days since 1–1–1 (forward to present)	[181, 9 130 878]	(max −vals)/365250
TraCE-21k	ka BP (stored negative)	[−22, 0.03]	−vals
CHELSA-TraCE21k-centennial	days since −20010−07−01 (forward)	[0, 8 035 335]	(max −vals)/365250

Table 4. Time-axis conventions and conversion to ka BP.

Dataset	Grid	Lat range	Lon range	Convention	Res.
Beyer2020	720 × 300	−59.75 ... 89.75	−179.75 ... 179.75	−180–180	0.5°
PalMod2	96 × 48 (Gaussian)	−87.16 ... 87.16	0 ... 356.25	0–360	~3.71/3.75°
TraCE-21k	96 × 48	−87.16 ... 87.16	0 ... 356.25	0–360	~3.71/3.75°
CHELSA-TraCE21k-centennial	global ~1 km	global	global	−180–180	0.0083°

Table 5. Spatial grids (authoritative native resolutions).

5. POINT EXTRACTION

The function `extract_temperature_at_point` returns a 1-D temperature series (in °C, on the ka BP axis) for one file at a requested coordinate. It (i) opens the file without decoding times; (ii) selects the nearest grid cell with `xarray.sel(method="nearest")` after translating the requested longitude into the file’s convention, a plain nearest-neighbour lookup with no interpolation, recording the actual cell-centre coordinates; (iii) collapses extra dimensions (keeps the topmost soil layer if a depth dimension is present, averages a month dimension to an annual mean); and (iv) converts kelvin to °C when needed. The same logic underlies the summary plots, so the text report, the time-series overlay and the grid-cell map cannot disagree about which cell was used.

6. INTER-MODEL COMPARISON METHOD

Beyond the single-point series, the tool produces global pairwise mean-difference heatmaps. For a pair of archives *A* and *B*: (1) a *shared time window* is computed from the two time axes (their overlap), read cheaply from the time coordinate alone, so both means cover the same interval; (2) a *common sampling grid* is used, namely every cell centre of the TraCE-21k grid ($96 \times 48 = 4608$ points), and for each archive the temperature at each point is read with a vectorised nearest-neighbour index, averaged over the shared window and converted to °C; (3) the difference $A - B$ is drawn on a PlateCarree world map with the diverging PRGn colormap and a TwoSlopeNorm centred at zero (green = *A* warmer, purple = *A* colder), and cells where either archive has no data (for example ocean cells for the terrestrial Beyer2020 and CHELSA-TraCE21k-centennial archives) remain blank.

Because the shared sampling grid is the *coarse* TraCE-21k grid, the high-resolution archives (Beyer2020 at 0.5°, CHELSA-TraCE21k-centennial at ~1 km) are effectively sub-sampled, one representative pixel per ~3.7° cell, rather than area-averaged into the coarse cell. This keeps the heatmaps fast

and memory-bounded but means they compare *point samples*, not area means (see Section 8.2). The point-extraction time-series plots, by contrast, use each archive at its native resolution; in particular CHELSA-TraCE21k-centennial is read at its full ~1 km grid, so the returned CHELSA-TraCE21k-centennial cell matches the requested point to within one ~1 km pixel ($\approx 0.0083^\circ$).

7. RESULTS

7.1 Air-temperature time series at the example point

Figure 1 shows that Beyer2020 (blue), the only archive spanning the full 120 kyr, reproduces the expected glacial-interglacial structure: a warm last interglacial (~9 °C around 120 ka), a long oscillating cooling, a cold interval around the LGM (dropping to $\approx -4^\circ\text{C}$ near 20–25 ka), and deglacial warming to ~8–9 °C in the Holocene; its 1–2 kyr step makes the curve smooth. PalMod2 (orange) and TraCE-21k (green) begin near the LGM and, at their native annual and decadal resolution, expose large high-frequency variability. CHELSA-TraCE21k-centennial (red) tracks the deglacial warming at centennial resolution and reaches the warmest late-Holocene values here. In the overlapping window the four agree on the shape of the signal but disagree on absolute temperature by several degrees; most conspicuously, TraCE-21k settles to a noticeably cooler Holocene plateau (~3 °C) than the other three (~7–9 °C), an offset of order 4–5 °C that recurs in the heatmaps below. Part of the offset is a scale artefact: the coarse GCMs return a ~3.7° cell centred at ~53.8°N, 11.25°E, which averages a large, partly maritime region, whereas Beyer2020 and CHELSA-TraCE21k-centennial resolve the land point itself (Fig. 3).

7.2 Soil-temperature time series at the example point

The soil comparison (Fig. 2) mirrors the air signal: both archives warm through the deglaciation, with PalMod2 again




Figure 1. Near-surface air-temperature time series at ≈ 53.26 N, 11.67 E (ka BP on the x -axis, $^{\circ}\text{C}$ on the y -axis), for all four archives. Each legend entry reports the grid-cell centre returned by the nearest-neighbour lookup.




Figure 2. Top-layer soil-temperature time series at the example point for PalMod2 and TraCE-21k (the only two archives with a soil variable).

showing much larger interannual spread and abrupt multi-millennial steps and a warmer Holocene soil temperature (~ 6 – 8 $^{\circ}\text{C}$) than TraCE-21k (~ 4 $^{\circ}\text{C}$, smoother). The systematic warm offset of PalMod2 relative to TraCE-21k echoes the air-temperature relationship and the high-latitude divergence seen globally.

7.3 Temporal coverage and the returned grid cells

These summary panels (Figs. 3–4) make the harmonisation challenge concrete. The coverage panel shows the three-order-of-magnitude spread in time step (Beyer $\Delta t \approx 2000$ yr, $n = 72$; PalMod2 ≈ 1 yr, $n = 25000$; TraCE-21k ≈ 10 yr, $n = 2204$; CHELSA-TraCE21k-centennial ≈ 100 yr, $n = 221$) and the very different coverage windows. The grid-cell panel shows the spatial-scale mismatch directly: the PalMod2 and TraCE-21k cells ($\sim 3.7^{\circ}$, overlapping exactly) form one large rectangle spanning much of northern Germany and the western Baltic, the Beyer2020 cell (0.05°) is small, and the CHELSA-TraCE21k-centennial (0.0083°) is effectively a point. The coarse cells visibly straddle land and sea, which biases their temperature relative to the high-resolution land-only archives.

7.4 Global pairwise difference heatmaps

The difference maps are computed on the shared $96 \times 48 = 4608$ -cell TraCE-21k grid described in Section 8.2.

Soil temperature. PalMod2 is markedly warmer than TraCE-21k across the high northern latitudes (northern Eurasia and North America, locally by ~ 10 – 15 $^{\circ}\text{C}$), with smaller patches where PalMod2 is cooler (Fig. 5). The dominant signal is a systematic high-latitude divergence between the two GCMs. TraCE-21k appears to be warmer in high mountain ranges such as the Himalayas and the Andes.

Air temperature, all six pairs. The four air archives yield six pairwise comparisons (Fig. 6), each averaged over the shared window noted in the panel. The maps show that Beyer2020 is generally warmer than PalMod2 across the tropics, mid-latitudes and mountain ranges but markedly colder over the high-northern continents (Fig. 6a); Beyer2020 is warmer than TraCE-21k almost everywhere, most strongly over northern Eurasia (Fig. 6b); Beyer2020 and CHELSA-TraCE21k-centennial, the two observation-anchored products, are the most similar pair, with only faint differences, except for high northern latitudes where CHELSA-TraCE21k-centennial is warmer in most cells (Fig. 6c); the two GCMs differ strongly and coherently, PalMod2 is much warmer than TraCE-21k at high northern latitudes and cooler over the Southern Ocean margin and in mountain ranges (Fig. 6d); PalMod2 – CHELSA-TraCE21k-centennial is moderate and patchy (Fig. 6e); and TraCE-21k is colder than CHELSA-TraCE21k-centennial across most land, again strongest in the high north (Fig. 6f).

Summary. Three robust patterns emerge: (1) TraCE-21k runs systematically cool relative to all three other archives, most strongly at high northern latitudes and at the example point; (2) the two coupled GCMs differ most, in a spatially coherent high-latitude dipole, indicating structural model differences rather than noise; (3) the two observation-anchored products agree most closely, reflecting their shared present-day observational baseline.

8. DISCUSSION

8.1 Sources of inter-model difference

The differences arise from several superimposed causes that the comparison cannot fully disentangle: (i) *model physics and forcing*, since CCSM3 and MPI-ESM1.2-CR are independent




Figure 3. Air archives. Left: temporal coverage (bar length = covered interval; annotation = time step and number of samples). Right: the grid cell each archive returns near the example point, drawn at its true size in degrees, over a regional basemap.




Figure 4. As Fig. 3, for the two soil archives (PalMod2, TraCE-21k).




Figure 5. Mean top-layer soil-temperature difference, PalMod2 — TraCE-21k, averaged over the shared 0–22 ka BP window (green = PalMod2 warmer, purple = PalMod2 colder).

models with different components, resolutions and deglacial forcing, so their large coherent high-latitude differences are genuine; (ii) *downscaling and bias correction*, since Beyer2020 and CHSLA-TraCE21k-centennial are anchored to present-day observations, which pulls their late-Holocene values toward a common baseline and explains why they agree best, while the raw GCMs can deviate strongly, especially over ice-marginal high latitudes; (iii) *variable definition*, since a model 2 m diagnostic, a downscaled monthly mean and the mean of down-

scaled daily extremes are close but not the same quantity; (iv) *spatial-scale mismatch*, since a $\sim 3.7^\circ$ cell averages a region that may mix land and ocean, whereas a ~ 1 km pixel resolves one landscape; and (v) *temporal resolution*, since annual to millennial sampling exposes very different amounts of variability.

8.2 Limitations and caveats

Nearest-neighbour sampling. Both the point extraction and the heatmaps use nearest-neighbour selection with no interpol-




Figure 6. Mean air-temperature differences for all six pairs of the four archives (green = first archive warmer, purple = colder), sampled at the TraCE-21k grid and averaged over each pair’s shared time window.

ation or area weighting; in the heatmaps the high-resolution archives are sub-sampled at coarse cell centres rather than averaged into them, so the maps compare representative point samples, not true area means. Conservative (area-mean) regrid-ding would be more rigorous but far more expensive at ~ 1 km. **Terrestrial vs global coverage.** Beyer2020 and CHESA-TraCE21k-centennial are land-only (Beyer2020 also excludes latitudes south of $\sim 60^\circ$ S); their ocean cells are blank, so any ocean signal in a pair involving them is absent by construction. **Single example point.** The time-series results characterise one mid-latitude continental location and should not be generalised; the tool is designed to be re-run anywhere. **Source-file metadata quirk.** In the published Beyer2020 NetCDF the units attributes of the two horizontal coordinates are transposed (longitude is labelled `degrees_north` and latitude `degrees_east`). This is a defect in the upstream file, not in the analysis: the tool identifies axes by name, not by their unit string, so results are unaffected.¹

¹ Visible in the per-dataset inspection output (`dataset_info.txt`, Beyer2020 block).

8.3 What the comparison shows

The exercise demonstrates both that these archives are hard to compare, since every dimension (variable, time, space, unit) requires explicit harmonisation before any number can be placed next to another, and that, once harmonised, the comparison is informative: it isolates a reproducible cool tendency in TraCE-21k, the strong structural disagreement between the two coupled GCMs at high latitudes, and the close agreement of the two observation-anchored products. These are exactly the systematic signals that flag where archives diverge and where modelling effort might be focused.

9. FUTURE WORK

Several extensions would sharpen the analysis. *Automated multi-point sampling* would iterate the extraction over many locations (or whole grids) and aggregate, rather than inspecting one point at a time. *Stratified analysis* would correlate the differences with latitude band, climate zone, land versus ocean, distance to former ice margins and elevation, moving from where the archives differ to why. *Area-weighted regrid-ding* would replace nearest-neighbour sampling in the heatmaps

with conservative regridding, so the high-resolution archives are compared as true area means. *Uncertainty* could be carried and displayed as the within-window temporal variability alongside the means, so an apparent offset can be judged against each archive's own variability. Finally, the comparison could be extended beyond temperature to precipitation and to the bioclimatic and vegetation fields available in Beyer2020.

10. CONCLUSION

Four heterogeneous paleoclimate temperature archives spanning the last glacial cycle were downloaded, pre-processed and harmonised onto a common ka BP time axis, a common unit (°C) and a common spatial framework, and then compared both at a point and globally. The principal difficulty is the harmonisation rather than the comparison: each archive uses a different time origin and sign convention, a different grid and longitude convention, a different temperature variable, and temporal and spatial resolutions differing by three orders of magnitude. A single time-conversion function, name-based axis detection, automatic longitude handling and unit conversion make the four directly comparable. Once harmonised, the archives agree on the first-order deglacial signal, a cold LGM followed by warming into the Holocene, but disagree on absolute temperature by several degrees, and the disagreements are neither random nor uniform: TraCE-21k is systematically cool, the two coupled GCMs diverge most strongly and coherently at high northern latitudes, and the two observation-anchored downscaling products agree most closely. The comparison cannot adjudicate which archive is correct, but it pinpoints where and by how much they differ, which is precisely the diagnostic value of inter-model comparison and a useful pointer toward where the underlying models or reconstructions most warrant scrutiny.

REFERENCES

- Beyer, R., 2021. Late Quaternary climate, bioclimate and vegetation. https://figshare.com/articles/dataset/LateQuaternary_Environment_nc/12293345. <https://doi.org/10.6084/m9.figshare.12293345.v4>.
- Beyer, R. M., Krapp, M., Manica, A., 2020. High-resolution terrestrial climate, bioclimate and vegetation for the last 120,000 years. <https://doi.org/10.1038/s41597-020-0552-1>.
- Beyer, R. M., Krapp, M., Manica, A., 2021. Addendum: High-resolution terrestrial climate, bioclimate and vegetation for the last 120,000 years. <https://doi.org/10.1038/s41597-021-01051-1>.
- CCSM3 TraCE simulations fields complete list, n.d. http://ccrlab21.aos.wisc.edu/~fenghe/pub/CCSM3_TraCE_simulations_complete_list.html. Accessed: 2026-06-14.
- Giersch, L. D. A., 2026. Paleoclimate Model Comparison. https://github.com/LevinGiersch/paleoclimate_model_comparison. Accessed: 2026-06-05.
- Karger, D. N., Nobis, M. P., Normand, S., Graham, C. H., Zimmermann, N. E., 2020. CHELSA-TraCE21k: Downscaled transient temperature and precipitation data since the last glacial maximum. https://www.envdat.ch/dataset/chelsa_trace. <https://doi.org/10.16904/envdat.211>.
- Karger, D. N., Nobis, M. P., Normand, S., Graham, C. H., Zimmermann, N. E., 2023. CHELSA-TraCE21k - high-resolution (1 km) downscaled transient temperature and precipitation data since the Last Glacial Maximum. <https://doi.org/10.5194/cp-19-439-2023>. Accessed: 2026-06-05.
- Mikolajewicz, U., Kapsch, M.-L., Gayler, V., Meccia, V. L., Riddick, T., Ziemann, F. A., Schannwell, C., 2023. PalMod2 MPI-M MPI-ESM1-2-CR Transient Simulations of the Last Deglaciation with prescribed ice sheets from GLAC-1D reconstructions (rli1plf1). <https://doi.org/10.26050/WDC/PMMXMCRTDGP111>. <https://doi.org/10.26050/WDC/PMMXMCRTDGP111>.
- Otto-Bliesner, B. L., Rosenbloom, N. A., 2021. Simulation of the Transient Climate of the Last 21,000 Years (TraCE-21ka). <https://gdex.ucar.edu/datasets/d651050/>. <https://doi.org/10.5065/CXB5-TV56>. Accessed: 2026-06-05.
- Wetterdienst, D., n.d. Klimadaten - wann wurde mit regelmäßigen und verlässlichen wetteraufzeichnungen begonnen? https://www.dwd.de/SharedDocs/faqs/DE/klima_faqqkarussell/klimadaten_1.html. Accessed: 2026-06-14.
- World Data Center for Climate and Deutsches Klimarechenzentrum, n.d. Jblob Documentation. <https://www.wdc-climate.de/ui/info?site=jblob>. Version 4.1. Accessed: 2026-06-05.